

Daniel Bernoulli.

JANDENUL.COM

Daniel Bernoulli.

DP2 Trenching and Offshore Support Vessel Subsea Rock Installation Vessel

Deadweight	5,950 t
Rock carrying capacity	approx. 4,750 t
Length o.a.	95 m
Breadth	22 m
Draught loaded	6.5 m
Dynamic positioning	DYNAPOS AM/AT R Class 2
Propulsion power	2 x 1,250 kW
Bow thruster power	2 x 1,250 kW
Total installed diesel power	7,670 kW
Speed	11.5 kn
Accommodation	60 persons (notation Special Purpose Ship)
Built in	2017
Max fall pipe depth	600 m
Inclined fall pipe diam.	1,000 mm / 1,800 mm
Inclined fall pipe length	45 m / 25 m
Offshore crane	40 t (25t AHC)
Rock loading capacity	1 Liebherr 984 excavator (1,000 ton/h)
Optional equipment	ROV Trencher Workclass ROV A-Frame





In the Subsea Rock Installation mode, the vessel can install approx. 4,750 t of rock in a single load by means of the excavator, conveyor belt and the fall pipe for accurate rock installation at up to 600 m water depth. Alternatively the rock can be handled through an inclined fall pipe, for secure installation against offshore structures such as jacket platforms, gravity bases or monopile foundations.

 $\mathsf{J} \mathsf{A} \mathsf{N} \mathsf{D} \mathsf{E} \mathsf{N} \mathsf{U} \mathsf{L}$. C 0 M

The content of this document is provided strictly for information purposes only. Whilst it has been endeavoured to procure completeness and accuracy, no warranty - express or implied - is given, in particular of fitness for a particular purpose. In no event any Jan De Nul Group company will be liable for any whatsoever damages arising directly or indirectly from the use of or reliance on the content provided herein, even if (previous) advice has been given/received that such damages may occur.

